BRUHATH BANGALORE MAHANAGARA PALIKE ,DASRAHALLI ZONE
Office Of The Executive Engineer, Dasarahalli Project Division
SCHEDULE-B

NAME OF THE WORK : Construction Of U Shape Drain For Secondary SWD in Mallasandra ward no 13

Sl No	Description Of Work	Unit	Qty	Rate to be Sanctioned	
				In Figures (Rs)	In Words (Rs)
1	2	3	4	5	6
1	Earth work in excavation for foundation of structures as per drawing and technical specifications, including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material complete as per specifications. "V. Marshy soil - B. Mechanical Means	Cum	872.10	236.30	Rupees Two Hundred Thirty Six And Paise Thirty Only
2	Providing and Filling in foundation with granite / trap broken metal 100mm. and down size, with approved sand including hand packing, ramming, watering, including cost of all materials and labour with all lead and lift. complete as per specifications.	Cum	102.60	2574.74	Rupees Two Thousand Five Hundred Seventy Four And Paise Seventy Four Only
3	Providing and laying Plain cement concrete of mix 1:3:6 with OPC @ 220kgs, with crushed 40mm and down size graded granite metal coarse aggregates @0.89cum and fine aggregates @ 0.46cum, in foundation mechanically mixed, placed in foundation and compacted by vibration including curing for 14 days including cost of all materials, labour, HOM curing, form works, scaffolding and centering complete as per specifications.	Cum	76.95	5421.90	Rupees Five Thousand Four Hundred Twenty One And Paise Ninety Only
4	Design mix M25 with OPC cement @ 340kgs, with 20mm and down size graded granite metal coarse aggregates @0.7cum and fine aggregates @ 0.47cum, with superplastisiser @3lts confirming to IS9103-1999 Reaffirmed-2008 - i) Upto 5m height	Cum	357.20	5640.26	Rupees Five Thousand Six Hundred Forty And Paise Twenty Six Only

Signature of the Contractor

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 010

Executive Engineer
Dasarahalli Project Division

Scanned by CamScanner

5	Providing T.M.T steel reinforcement for R.C.C workincluding straightening, cutting, bending, hooking, placing in position,lapping and / or welding wherever required, tying with binding wire andanchoring to the adjoining members wherever necessary complete asper design (laps, hooks and wastage shall not be measured and paid)cost of materials, labour, HOM of machinery complete as perspecifications.	Tonne	35.72	75223.96	Rupees Seventy Five Thousand Two Hundred Twenty Three And Paise Ninety Six Only
6	Providing weep holes in Brick masonry / Plain / Reinforced concrete abutment, wing wall / return wall with 100 mm dia AC pipe, extending through the full width of the structure with slope of 1V :20H towards drawing foce. Complete as per drawing and Technical Specifications complete as per specifications	No/Mtr	288.00	155.82	Rupees One Hundred Fifty Five And Paise Eighty Two Only
7	Supplying and fixing M.S. Rectangular poles made out of 2 equal angles of 65x65x6 mm welded together and fixed in CC (1:2:4) WITH 2 NOS 16mm dia M.S. hold fast rods each of length 25 cms. Including cost of all materialscutting, bending scaffolding wherever necessary, nicely finishing the weldedjoints with all lead lifts and as per the directions of the Engineer-in - charge of the work and including providing 2 coats of approved quality paint over one coat of shop painting (excluding cost of earthwork and concrete)	Mtr	570.00	927.72	Rupees Nine Hundred Twenty Seven And Paise Seventy Two Only
8	Providing and fixing M.S. Block pipe of 38mm dia, of heavy guage of 14 including removing the bends, cutting the pipe, and fixing pipe in between / the existing two verticle poles (M.S. rectangular poles) and spot welding the chain link with M.S. block pipe including cost of all materials wastage in cutting, and scaffolding wherever necessary with all lead and lift as directed by the Engineer-in-charge of work etc., complete including two coats of approved quality paint over one coat of shop paint.	Mtr	1140.00	440.64	Rupees Four Hundred Forty And Paise Sixty Four Only
9	Providing chain link fencing 50mm size of 8 guage properly stretched between existing rectangular poles and fixed with suitable bolts & nuts, the free ends shall be welded to the pole and block pipe at top and bottom as required including cost of all materials, labour, lead and lifts and as per the directions of the Engineer-in-charge of work including two coats of approved quality paint over one coat of shop paint specification.	Sqm	874.00	772.20	Rupees Seven Hundred Seventy Two And Paise Twenty Only

Signature Of The Contractor

EXECUTIVE ENGINEER-5
KRIDL, BMP DIVISION
BENGALURU-560 010

Executive Engineer
Dasarahalli Project Division

Scanned by CamScanner